CERTIFICATE OF ANALYSIS

REPORTED TO	Cherry Ridge Management 158 North Fork Road Cherryville, BC V0E 2G3		
ATTENTION	Melanie Staker	**WORK ORDER**	24K1965
PO NUMBER	Cherry Ridge Management Creek Monitoring	**RECEIVED / TEMP**	2024-11-18 09:03 / 4.6°C
PROJECT	Creek Monitoring	**REPORTED**	2024-11-25 09:53
PROJECT INFO		**COC NUMBER**	No Number

Introduction:

CARO Analytical Services is a testing laboratory full of smart, engaged scientists driven to make the world a safer and healthier place. Through our clients' projects we become an essential element for a better world. We employ methods conducted in accordance with recognized professional standards using accepted testing methodologies and quality control efforts. CARO is accredited by the Canadian Association for Laboratories Accreditation (CALA) to ISO/IEC 17025:2017 for specific tests listed in the scope of accreditation approved by CALA.

Big Picture Sidekicks

You know that the sample you collected after snowshoeing to site, digging 5 meters, and racing to get it on a plane so you can submit it to the lab for time sensitive results needed to make important and expensive decisions (whew) is VERY important. We know that too.

We've Got Chemistry

It's simple. We figure the more you enjoy working with our fun and engaged team members; the more likely you are to give us continued opportunities to support you.

Ahead of the Curve

Through research, regulation knowledge, and instrumentation, we are your analytical centre for the technical knowledge you need, BEFORE you need it, so you can stay up to date and in the know.

By engaging our services, you are agreeing to CARO Analytical Service's Standard Terms and Conditions outlined here: https://www.caro.ca/terms-conditions

If you have any questions or concerns, please contact me at TeamCaro@caro.ca

Authorized By:

Team CARO
Client Service Representative

CARO ANALYTICAL SERVICES

TEST RESULTS

REPORTED TO	Cherry Ridge Management	**WORK ORDER**	24K1965
PROJECT	Creek Monitoring	**REPORTED**	2024-11-25 09:53

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
Ferry Creek (24K1965-01) | Matrix: Water | Sampled: 2024-11-17 10:35						PRES
Anions						
Chloride	**1.06**	AO ≤ 250	0.10	mg/L	2024-11-19	
Nitrate (as N)	**0.013**	MAC = 10	0.010	mg/L	2024-11-19	
Nitrite (as N)	< 0.010	MAC = 1	0.010	mg/L	2024-11-19	
Sulfate	**29.9**	AO ≤ 500	1.0	mg/L	2024-11-19	
Calculated Parameters						
Nitrate+Nitrite (as N)	**0.0127**	N/A	0.0100	mg/L	N/A	
Nitrogen, Total	**0.139**	N/A	0.0500	mg/L	N/A	
Dissolved Metals						
Aluminum, dissolved	**0.0065**	N/A	0.0050	mg/L	2024-11-19	
General Parameters						
Conductivity (EC)	**315**	N/A	2.0	µS/cm	2024-11-19	
Nitrogen, Total Kjeldahl	**0.126**	N/A	0.050	mg/L	2024-11-21	
pH	**8.29**	7.0-10.5	0.10	pH units	2024-11-19	HT2
Phosphorus, Total (as P)	**0.0117**	N/A	0.0050	mg/L	2024-11-21	
Phosphorus, Total Dissolved	**0.0102**	N/A	0.0050	mg/L	2024-11-21	
Turbidity	**0.34**	OG < 1	0.10	NTU	2024-11-18	
Microbiological Parameters						
Coliforms, Total (Q-Tray)	**201**	MAC = 0	1	MPN/100 mL	2024-11-18	
E. coli (Q-Tray)	**5**	MAC = 0	1	MPN/100 mL	2024-11-18	
Shuswap River (24K1965-02) | Matrix: Water | Sampled: 2024-11-17 10:15						PRES
Anions						
Chloride	**0.32**	AO ≤ 250	0.10	mg/L	2024-11-19	
Nitrate (as N)	**0.050**	MAC = 10	0.010	mg/L	2024-11-19	
Nitrite (as N)	< 0.010	MAC = 1	0.010	mg/L	2024-11-19	
Sulfate	**5.1**	AO ≤ 500	1.0	mg/L	2024-11-19	
Calculated Parameters						
Nitrate+Nitrite (as N)	**0.0497**	N/A	0.0100	mg/L	N/A	
Nitrogen, Total	**0.255**	N/A	0.0500	mg/L	N/A	
Dissolved Metals						
Aluminum, dissolved	**0.0293**	N/A	0.0050	mg/L	2024-11-19	
General Parameters						
Conductivity (EC)	**90.5**	N/A	2.0	µS/cm	2024-11-19	
Nitrogen, Total Kjeldahl	**0.205**	N/A	0.050	mg/L	2024-11-21	
pH	**7.81**	7.0-10.5	0.10	pH units	2024-11-19	HT2
Phosphorus, Total (as P)	**0.0069**	N/A	0.0050	mg/L	2024-11-21	
Phosphorus, Total Dissolved	**0.0090**	N/A	0.0050	mg/L	2024-11-21	

CARO ANALYTICAL SERVICES

TEST RESULTS

REPORTED TO	Cherry Ridge Management	**WORK ORDER**	24K1965
PROJECT	Creek Monitoring	**REPORTED**	2024-11-25 09:53

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
Shuswap River (24K1965-02) | Matrix: Water | Sampled: 2024-11-17 10:15, Continued						PRES
General Parameters, Continued						
Turbidity	**0.84**	OG < 1	0.10	NTU	2024-11-18	
Microbiological Parameters						
Coliforms, Total (Q-Tray)	**210**	MAC = 0	1	MPN/100 mL	2024-11-18	
E. coli (Q-Tray)	**9**	MAC = 0	1	MPN/100 mL	2024-11-18	
1/2 Mile Creek (24K1965-03) | Matrix: Water | Sampled: 2024-11-17 12:08						PRES
Anions						
Chloride	**0.31**	AO ≤ 250	0.10	mg/L	2024-11-19	
Nitrate (as N)	< 0.010	MAC = 10	0.010	mg/L	2024-11-19	
Nitrite (as N)	< 0.010	MAC = 1	0.010	mg/L	2024-11-19	
Sulfate	**41.2**	AO ≤ 500	1.0	mg/L	2024-11-19	
Calculated Parameters						
Nitrate+Nitrite (as N)	< 0.0100	N/A	0.0100	mg/L	N/A	
Nitrogen, Total	**0.0620**	N/A	0.0500	mg/L	N/A	
Dissolved Metals						
Aluminum, dissolved	< 0.0050	N/A	0.0050	mg/L	2024-11-19	
General Parameters						
Conductivity (EC)	**416**	N/A	2.0	µS/cm	2024-11-19	
Nitrogen, Total Kjeldahl	**0.062**	N/A	0.050	mg/L	2024-11-21	
pH	**8.26**	7.0-10.5	0.10	pH units	2024-11-19	HT2
Phosphorus, Total (as P)	**0.0159**	N/A	0.0050	mg/L	2024-11-21	
Phosphorus, Total Dissolved	**0.0086**	N/A	0.0050	mg/L	2024-11-21	
Turbidity	**0.27**	OG < 1	0.10	NTU	2024-11-18	
Microbiological Parameters						
Coliforms, Total (Q-Tray)	**9**	MAC = 0	1	MPN/100 mL	2024-11-18	
E. coli (Q-Tray)	< 1	MAC = 0	1	MPN/100 mL	2024-11-18	
Cherry Creek at Hall (24K1965-04) | Matrix: Water | Sampled: 2024-11-17 11:42						PRES
Anions						
Chloride	**1.93**	AO ≤ 250	0.10	mg/L	2024-11-19	
Nitrate (as N)	**0.050**	MAC = 10	0.010	mg/L	2024-11-19	
Nitrite (as N)	< 0.010	MAC = 1	0.010	mg/L	2024-11-19	
Sulfate	**14.2**	AO ≤ 500	1.0	mg/L	2024-11-19	
Calculated Parameters						
Nitrate+Nitrite (as N)	**0.0505**	N/A	0.0100	mg/L	N/A	
Nitrogen, Total	**0.152**	N/A	0.0500	mg/L	N/A	

CARO ANALYTICAL SERVICES

TEST RESULTS

REPORTED TO	Cherry Ridge Management	**WORK ORDER**	24K1965
PROJECT	Creek Monitoring	**REPORTED**	2024-11-25 09:53

Analyte	Result	Guideline	RL	Units	Analyzed	Qualifier
Cherry Creek at Hall (24K1965-04) | Matrix: Water | Sampled: 2024-11-17 11:42, Continued						PRES
Dissolved Metals						
Aluminum, dissolved	**0.0574**	N/A	0.0050	mg/L	2024-11-19	
General Parameters						
Conductivity (EC)	**220**	N/A	2.0	µS/cm	2024-11-19	
Nitrogen, Total Kjeldahl	**0.102**	N/A	0.050	mg/L	2024-11-21	
pH	**8.17**	7.0-10.5	0.10	pH units	2024-11-19	HT2
Phosphorus, Total (as P)	**0.0167**	N/A	0.0050	mg/L	2024-11-21	
Phosphorus, Total Dissolved	**0.0130**	N/A	0.0050	mg/L	2024-11-21	
Turbidity	**1.77**	OG < 1	0.10	NTU	2024-11-18	
Microbiological Parameters						
Coliforms, Total (Q-Tray)	**77**	MAC = 0	1	MPN/100 mL	2024-11-18	
E. coli (Q-Tray)	**3**	MAC = 0	1	MPN/100 mL	2024-11-18	
N. Fork (24K1965-05) | Matrix: Water | Sampled: 2024-11-17 11:15						PRES
Anions						
Chloride	**0.15**	AO ≤ 250	0.10	mg/L	2024-11-19	
Nitrate (as N)	**0.024**	MAC = 10	0.010	mg/L	2024-11-19	
Nitrite (as N)	< 0.010	MAC = 1	0.010	mg/L	2024-11-19	
Sulfate	**9.6**	AO ≤ 500	1.0	mg/L	2024-11-19	
Calculated Parameters						
Nitrate+Nitrite (as N)	**0.0242**	N/A	0.0100	mg/L	N/A	
Nitrogen, Total	**0.0922**	N/A	0.0500	mg/L	N/A	
Dissolved Metals						
Aluminum, dissolved	**0.0128**	N/A	0.0050	mg/L	2024-11-19	
General Parameters						
Conductivity (EC)	**157**	N/A	2.0	µS/cm	2024-11-19	
Nitrogen, Total Kjeldahl	**0.068**	N/A	0.050	mg/L	2024-11-21	
pH	**8.02**	7.0-10.5	0.10	pH units	2024-11-19	HT2
Phosphorus, Total (as P)	**0.0059**	N/A	0.0050	mg/L	2024-11-21	
Phosphorus, Total Dissolved	< 0.0050	N/A	0.0050	mg/L	2024-11-21	
Turbidity	**0.41**	OG < 1	0.10	NTU	2024-11-18	
Microbiological Parameters						
Coliforms, Total (Q-Tray)	**42**	MAC = 0	1	MPN/100 mL	2024-11-18	
E. coli (Q-Tray)	**1**	MAC = 0	1	MPN/100 mL	2024-11-18	

TEST RESULTS

REPORTED TO	Cherry Ridge Management	**WORK ORDER**	24K1965
PROJECT	Creek Monitoring	**REPORTED**	2024-11-25 09:53

Sample Qualifiers:

HT2	The 15 minute recommended holding time (from sampling to analysis) has been exceeded - field analysis is recommended.
PRES	Sample has been preserved for TKN, TP in the laboratory and the holding time has been extended.

APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO	Cherry Ridge Management	**WORK ORDER**	24K1965
PROJECT	Creek Monitoring	**REPORTED**	2024-11-25 09:53

Analysis Description	Method Ref.	Technique	Accredited	Location
Anions in Water	SM 4110 B (2020)	Ion Chromatography	✓	Kelowna
Coliforms, Total in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
Conductivity in Water	SM 2510 B (2021)	Conductivity Meter	✓	Kelowna
Dissolved Metals in Water	EPA 200.8 / EPA 6020B	0.45 µm Filtration / Inductively Coupled Plasma-Mass Spectroscopy (ICP-MS)	✓	Richmond
E. coli in Water	SM 9223 (2016)	Quanti-Tray / Enzyme Substrate Endo Agar	✓	Kelowna
Nitrogen, Total Kjeldahl in Water	SM 4500-Norg D* (2021)	Block Digestion and Flow Injection Analysis	✓	Kelowna
pH in Water	SM 4500-H+ B (2021)	Electrometry	✓	Kelowna
Phosphorus, Total Dissolved in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Phosphorus, Total in Water	SM 4500-P B.5* (2011) / SM 4500-P F (2021)	Persulfate Digestion / Automated Colorimetry (Ascorbic Acid)	✓	Kelowna
Turbidity in Water	SM 2130 B (2020)	Nephelometry	✓	Kelowna

Note: An asterisk in the Method Reference indicates that the CARO method has been modified from the reference method

Glossary of Terms:

RL	Reporting Limit (default)
<	Less than the specified Reporting Limit (RL) - the actual RL may be higher than the default RL due to various factors
AO	Aesthetic Objective
MAC	Maximum Acceptable Concentration (health based)
mg/L	Milligrams per litre
MPN/100 mL	Most Probable Number per 100 millilitres
NTU	Nephelometric Turbidity Units
OG	Operational Guideline (treated water)
pH units	pH < 7 = acidic, ph > 7 = basic
µS/cm	Microsiemens per centimetre
EPA	United States Environmental Protection Agency Test Methods
SM	Standard Methods for the Examination of Water and Wastewater, American Public Health Association

Guidelines Referenced in this Report:

Guidelines for Canadian Drinking Water Quality (Health Canada, September 2022)

Note: In some cases, the values displayed on the report represent the lowest guideline and are to be verified by the end user

APPENDIX 1: SUPPORTING INFORMATION

REPORTED TO	Cherry Ridge Management	**WORK ORDER**	24K1965
PROJECT	Creek Monitoring	**REPORTED**	2024-11-25 09:53

General Comments:

The results in this report apply to the received samples analyzed in accordance with the Chain of Custody document. This analytical report must be reproduced in its entirety. CARO is not responsible for any loss or damage resulting directly or indirectly from error or omission in the conduct of testing. Liability is limited to the cost of analysis. Caro will dispose of all samples within 30 days of sample receipt, unless otherwise agreed.

Results in **Bold** indicate values that are above CARO's method reporting limits. Any results that are above regulatory limits are highlighted **red**. Please note that results will only be highlighted red if the regulatory limits are included on the CARO report. Any Bold and/or highlighted results do not take into account method uncertainty. If you would like method uncertainty or regulatory limits to be included on your report, please contact your Account Manager: TeamCaro@caro.ca

Please note any regulatory guidelines applied to this report are added as a convenience to the client, at their request, to help provide some initial context to analytical results obtained. Although CARO makes every effort to ensure accuracy of the associated regulatory guideline(s) applied, the guidelines applied cannot be assumed to be correct due to a variety of factors and as such CARO Analytical Services assumes no liability or responsibility for the use of those guidelines to make any decisions. The original source of the regulation should be verified and a review of the guideline(s) should be validated as correct in order to make any decisions arising from the comparison of the analytical data obtained to the relevant regulatory guideline for one's particular circumstances. Further, CARO Analytical Services assumes no liability or responsibility for any loss attributed from the use of these guidelines in any way.

APPENDIX 2: QUALITY CONTROL RESULTS

REPORTED TO	Cherry Ridge Management	**WORK ORDER**	24K1965
PROJECT	Creek Monitoring	**REPORTED**	2024-11-25 09:53

The following section displays the quality control (QC) data that is associated with your sample data. Groups of samples are prepared in "batches" and analyzed in conjunction with QC samples that ensure your data is of the highest quality. Common QC types include:

- **Method Blank (Blk)**: A blank sample that undergoes sample processing identical to that carried out for the test samples. Method blank results are used to assess contamination from the laboratory environment and reagents.
- **Duplicate (Dup)**: An additional or second portion of a randomly selected sample in the analytical run carried through the entire analytical process. Duplicates provide a measure of the analytical method's precision (reproducibility).
- **Blank Spike (BS)**: A sample of known concentration which undergoes processing identical to that carried out for test samples, also referred to as a laboratory control sample (LCS). Blank spikes provide a measure of the analytical method's accuracy.
- **Matrix Spike (MS)**: A second aliquot of sample is fortified with a known concentration of target analytes and carried through the entire analytical process. Matrix spikes evaluate potential matrix effects that may affect the analyte recovery.
- **Reference Material (SRM)**: A homogenous material of similar matrix to the samples, certified for the parameter(s) listed. Reference Materials ensure that the analytical process is adequate to achieve acceptable recoveries of the parameter(s) tested.

Each QC type is analyzed at a 5-10% frequency, i.e. one blank/duplicate/spike for every 10-20 samples. For all types of QC, the specified recovery (% Rec) and relative percent difference (RPD) limits are derived from long-term method performance averages and/or prescribed by the reference method.

Analyte	Result	RL	Units	Spike Level	Source Result	% REC	REC Limit	% RPD	RPD Limit	Qualifier
Anions, Batch B4K3016										
Blank (B4K3016-BLK1)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Chloride	< 0.10	0.10	mg/L							
Nitrate (as N)	< 0.010	0.010	mg/L							
Nitrite (as N)	< 0.010	0.010	mg/L							
Sulfate	< 1.0	1.0	mg/L							
LCS (B4K3016-BS1)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Chloride	15.8	0.10	mg/L	16.0		99	90-110			
Nitrate (as N)	3.91	0.010	mg/L	4.00		98	90-110			
Nitrite (as N)	1.97	0.010	mg/L	2.00		98	85-115			
Sulfate	15.7	1.0	mg/L	16.0		98	90-110			
Dissolved Metals, Batch B4K3079										
Blank (B4K3079-BLK1)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Aluminum, dissolved	< 0.0050	0.0050	mg/L							
LCS (B4K3079-BS1)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Aluminum, dissolved	4.01	0.0050	mg/L	4.00		100	80-120			
Dissolved Metals, Batch B4K3087										
Blank (B4K3087-BLK1)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Aluminum, dissolved	< 0.0050	0.0050	mg/L							
LCS (B4K3087-BS1)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Aluminum, dissolved	4.01	0.0050	mg/L	4.00		100	80-120			
General Parameters, Batch B4K2949										
Blank (B4K2949-BLK1)				Prepared: 2024-11-18, Analyzed: 2024-11-18						
Turbidity	< 0.10	0.10	NTU							
LCS (B4K2949-BS1)				Prepared: 2024-11-18, Analyzed: 2024-11-18						
Turbidity	146	0.10	NTU	140		104	90-110			

APPENDIX 2: QUALITY CONTROL RESULTS

REPORTED TO	Cherry Ridge Management	**WORK ORDER**	24K1965
PROJECT	Creek Monitoring	**REPORTED**	2024-11-25 09:53

Analyte	Result	RL	Units	Spike Level	Source Result	% REC	REC Limit	% RPD	RPD Limit	Qualifier
General Parameters, Batch B4K2952										
Blank (B4K2952-BLK1)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Conductivity (EC)	< 2.0	2.0	µS/cm							BLK
Blank (B4K2952-BLK2)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Conductivity (EC)	< 2.0	2.0	µS/cm							BLK
Blank (B4K2952-BLK3)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Conductivity (EC)	< 2.0	2.0	µS/cm							BLK
LCS (B4K2952-BS2)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Conductivity (EC)	1400	2.0	µS/cm	1410		99	95-105			
LCS (B4K2952-BS4)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Conductivity (EC)	1400	2.0	µS/cm	1410		99	95-105			
LCS (B4K2952-BS6)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
Conductivity (EC)	1400	2.0	µS/cm	1410		99	95-105			
Reference (B4K2952-SRM1)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
pH	7.02	0.10	pH units	7.01		100	98-102			
Reference (B4K2952-SRM2)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
pH	7.02	0.10	pH units	7.01		100	98-102			
Reference (B4K2952-SRM3)				Prepared: 2024-11-19, Analyzed: 2024-11-19						
pH	7.02	0.10	pH units	7.01		100	98-102			
General Parameters, Batch B4K3223										
Blank (B4K3223-BLK1)				Prepared: 2024-11-20, Analyzed: 2024-11-21						
Nitrogen, Total Kjeldahl	< 0.050	0.050	mg/L							
Blank (B4K3223-BLK2)				Prepared: 2024-11-20, Analyzed: 2024-11-21						
Nitrogen, Total Kjeldahl	< 0.050	0.050	mg/L							
LCS (B4K3223-BS1)				Prepared: 2024-11-20, Analyzed: 2024-11-21						
Nitrogen, Total Kjeldahl	1.05	0.050	mg/L	1.00		105	85-115			
LCS (B4K3223-BS2)				Prepared: 2024-11-20, Analyzed: 2024-11-21						
Nitrogen, Total Kjeldahl	1.04	0.050	mg/L	1.00		104	85-115			
Duplicate (B4K3223-DUP2)			**Source: 24K1965-01**	Prepared: 2024-11-20, Analyzed: 2024-11-21						
Nitrogen, Total Kjeldahl	0.103	0.050	mg/L		0.126				15	
Matrix Spike (B4K3223-MS2)			**Source: 24K1965-01**	Prepared: 2024-11-20, Analyzed: 2024-11-21						
Nitrogen, Total Kjeldahl	1.14	0.050	mg/L	1.00	0.126	101	65-135			
General Parameters, Batch B4K3282										
Blank (B4K3282-BLK1)				Prepared: 2024-11-21, Analyzed: 2024-11-21						
Phosphorus, Total (as P)	< 0.0050	0.0050	mg/L							
Phosphorus, Total Dissolved	< 0.0050	0.0050	mg/L							
LCS (B4K3282-BS1)				Prepared: 2024-11-21, Analyzed: 2024-11-21						
Phosphorus, Total (as P)	0.101	0.0050	mg/L	0.100		101	85-115			
Phosphorus, Total Dissolved	0.100	0.0050	mg/L	0.100		100	85-115			

APPENDIX 2: QUALITY CONTROL RESULTS

REPORTED TO	Cherry Ridge Management	**WORK ORDER**	24K1965
PROJECT	Creek Monitoring	**REPORTED**	2024-11-25 09:53

Analyte	Result	RL	Units	Spike Level	Source Result	% REC	REC Limit	% RPD	RPD Limit	Qualifier
General Parameters, Batch B4K3282, Continued										
Duplicate (B4K3282-DUP1)		**Source: 24K1965-03**		Prepared: 2024-11-21, Analyzed: 2024-11-21						
Phosphorus, Total (as P)	0.0065	0.0050	mg/L		0.0159				15	
Phosphorus, Total Dissolved	0.0053	0.0050	mg/L		0.0086				15	
Matrix Spike (B4K3282-MS1)		**Source: 24K1965-03**		Prepared: 2024-11-21, Analyzed: 2024-11-21						
Phosphorus, Total (as P)	0.119	0.0050	mg/L	0.102	0.0159	101	70-125			
Phosphorus, Total Dissolved	0.108	0.0050	mg/L	0.102	0.0086	97	70-125			
Microbiological Parameters, Batch B4K2953										
Blank (B4K2953-BLK1)				Prepared: 2024-11-18, Analyzed: 2024-11-18						
Coliforms, Total (Q-Tray)	< 1	1	MPN/100 mL							
E. coli (Q-Tray)	< 1	1	MPN/100 mL							
Blank (B4K2953-BLK3)				Prepared: 2024-11-18, Analyzed: 2024-11-18						
Coliforms, Total (Q-Tray)	< 1	1	MPN/100 mL							
E. coli (Q-Tray)	< 1	1	MPN/100 mL							
Duplicate (B4K2953-DUP3)		**Source: 24K1965-01**		Prepared: 2024-11-18, Analyzed: 2024-11-18						
Coliforms, Total (Q-Tray)	219	1	MPN/100 mL		201			8	80	
E. coli (Q-Tray)	4	1	MPN/100 mL		5			24	80	

QC Qualifiers:

BLK Analyte concentration in the Method Blank is above the Reporting Limit (RL).